Astra Engineering Consultancy Pvt. Ltd

SUMMARY OF COST

S.N.	Description	Items	Amount	Remarks
	Design and Supervision			
	INTERIOR Work			
1	Reception Area	1 nos.	669,487.10	
2	Coffee lounge	1 nos.	591,770.88	
3	Locker Space	1 nos.	1,524,552.00	
4	Studio	1 nos.	1,964,709.40	
5	Changing Room	1 nos.	258,127.80	
6	Washroom	1 nos.	42,501.50	
7	Laminate Flooring	1nos.	550,000.00	
	Total		5,601,148.68	
4	Electrical Works	1 nos	280,057.43	
		Sub Total =	**5,881,206.11**	
		VAT 13%	764,556.79	
		Grand Total:	**6,645,762.90**	

AOC

SN	Description	Unit	No	Quantity	Rate	Amount	Remarks
1	Providing, supplying and placing curved Shaped Cupboard including formica necessary partitions, shelves and all hardware accessories, complete with polishing/painting and all works as per approved design, detail drawings, and instruction of the Site Engineer.	sq ft	1	22.43	2450.00	54953.5	
2	Providing, supplying and placing marble slab with adhesive, polishing/painting, complete in all respects as per approved design and instruction of the Site Engineer.	sq ft	1	44.26	750.00	33195	
3	Providing, supplying and placing reception desk with WPC panel and complete finish, including all necessary accessories, fittings, and fixtures, complete as per approved design and instruction of the Site Engineer.	sq ft	1	44.41	2800.00	124348	
4	Providing, supplying and placing Shoe rack with complete finish, including all necessary fittings, accessories, and fixtures, complete as per approved design and instruction of the Site Engineer.	sq ft	1	14.33	2650.00	37974.5	
5	Providing, supplying and placing ratten board with complete finish, including all necessary fittings, accessories, and fixtures, complete as per approved design and instruction of the Site Engineer.	sq ft	1	14.33	1900.00	27227	
6	Providing, supplying and fixing glass door with all necessary ftiings and materials as approved by design and instruction of site engineer	sq ft	1	0.00	1700.00	0	
7	Providing and fixing AC of 1.5 MT capacity with all necessary electrical works,support frame as approved by the design and instruction of site engineer	Nos	1	1.00	110000.00	110000	
8	Providing and laying Strip lighting with all necessary electrical works as approved by the design and instruction of site engineer	R.ft	1	73.99	300.00	22197	
9	Providing, supplying and installing ceiling-mounted lights,Wardrobe lights including wiring connection, fittings, accessories, and all related electrical works, complete as per approved design and instruction of the Site Engineer	Nos	1	7	1500.00	10500	
10	Providing, supplying and installing Chandelier including wiring connection, fittings, accessories, and all related electrical works, complete as per approved design and instruction of the Site Engineer	Nos.	1	1	35000.00	35000	
10	Providing and applying wall putty with paintingon prepared plastered surface to achieve smooth finish, including necessary surface preparation, sanding, and finishing, complete as per approved design and instruction of the Site Engineer.	sq ft	1	235	190.00	44650	
11	Providing, supplying and installing Gypsum Board with points for ceiling mounted lights	SQ FT	1	279.614	150.00	41942.1	
12	Providing, supplying and installing Signage Board with Brand Name	No.	1	2	10000.00	20000	
13	Providing, supplying and installing false ceiling with points for ceiling mounted lights	point	1	5	4500.00	22500	

AOC

SN	Description	Unit	No	Quantity	Rate	Amount	Remarks
14	Providing and installing couch in reception area as per the instruction of site engineer		**1**	**2**	**25000.00**	**50000**	
15	Providing and installation of granite centre table all complete with necessary fixtures as per the instruction of site engineer	**nos.**	**1**	**1**	**35000.00**	**35000**	
					Total	**669487.1**	

AOC

SN	Description	Unit	No	Quantity	Rate	Amount	Remarks
1	Providing, supplying and placing Sofa with hardwood frame and laminated/commercial board finish with appropriate thick sponges, fabrics and cushions, complete with polishing/painting and all necessary accessories as per design and instruction of the Site Engineer.	No	1	1.00	95000.00	95000	
2	Providing, supplying and placing marble slab with adhesive, polishing/painting, complete in all respects as per approved design and instruction of the Site Engineer.	Sq ft	1	110.57	750.00	82927.5	
3	Providing, supplying and fixing counter table, including necessary fixing arrangements, adhesive, polishing/painting, and all hardware accessories, complete in all respects as per approved design and instruction of the Site Engineer.	Sq ft	1	38.27	2750.00	105242.5	
4	Providing, supplying and installing counter skirting counter with complete fixing and finish, including all necessary fittings, accessories, and fixtures, complete as per approved design and instruction of the Site Engineer.	Rft	1	15.50	750.00	11625	
6	Providing and fixing PVC panel for including all necessary fixing accessories, and finishing works, complete as per approved design and instruction of the Site Engineer.	sq ft	1	159.62	450.00	71829	
7	Providing, supplying and installing ceiling-mounted lights including wiring connection, fittings, accessories, and all related electrical works, complete as per approved design and instruction of the Site Engineer	Nos	1	15.00	1500.00	22500	
8	Providing and applying wall putty with painting on prepared plastered surface to achieve smooth finish, including necessary surface preparation, sanding, and finishing, complete as per approved design and instruction of the Site Engineer.	sq ft	1	152.50	190.00	28975	
9	Providing, supplying and installing 1-ton split air conditioner of specified brand with indoor and outdoor units, copper piping, drain pipe, electrical connections, and necessary fittings, complete as per approved design and instruction of the Site Engineer.	No	1	1	85000.00	85000	
10	Providing, supplying and installing false ceiling with points for ceiling mounted lights	Sq ft	1	84.8125	150.00	12721.88	
11	Supplying and fixing of irregular glass table with sitting tool	Nos.	1	1	40000.00	40000	
12	Providing and laying Strip lighting with all necessary fixtures works as approved by the design and instruction of site engineer	Rft	1	11.50	300.00	3450	
14	Providing and installing of hanging lights with all necessary fixtures as approved by the design and instruction of site engineer	nos.	1	1.00	7500.00	7500	
15	Supplying and fixing of kitchen sink including all necessary fixtures including water tap as per the instruction of site engineer	nos.	1	1.00	25000.00	25000	
		Total				591770.9	

SN	Description	Unit	No	Quantity	Rate	Amount	Remarks
1	Providing, supplying and fixing Lockers with plywood and formica includingall necessary accessories, complete in all respects as per approved design and instruction of the Site Engineer.	sq ft	1	69.38	2500.00	173450	
2	Providing, supplying and fixing Cleaning Supply Closet with plywood and formica including all necessary accessories, complete in all respects as per approved design and instruction of the Site Engineer.	sq ft	1	35.00	2500.00	87500	
3	Providing and fixing PVCpanels including all necessary framing, fixing accessories, and finishing works, complete as per approved design and instruction of the Site Engineer.	sq ft	1	115.47	1350.00	155884.5	
4	Providing, supplying and installing hanging lights including wiring connection, fittings, accessories, and all related electrical works, complete as per approved design and instruction of the Site Engineer	Nos	1	2.00	7500.00	15000	
5	Providing and applying wall putty on prepared plastered surface to achieve smooth finish, including necessary surface preparation, sanding, and finishing, complete as per approved design and instruction of the Site Engineer.	sq ft	1	880	190.00	167200	
6	Providing, supplying and installing 1-ton split air conditioner of specified brand with indoor and outdoor units, copper piping, drain pipe, electrical connections, and necessary fittings, complete as per approved design and instruction of the Site Engineer	No	1	1	85000.00	85000	
7	Providing, supplying and installing Curved Gypsum Board with all necessary fixtures as per the instruction os site engineer	Sqft	1	356.50	195	69517.5	
8	Providing and laying Strip lighting with all necessary electrical works as approved by the design and instruction of site engineer	Rft.	1	44.00	300	13200	
10	Providing, supplying and installing Signage Board with Brand Name	Nos.	1	2.00	10000	20000	
12	Providing and fixing sliding doors all complete with all necessary fixtures as per the instruction of site engineer	Sqft	1	434.00	1700	737800	
				TOTAL:		1524552	

SN	Description	Unit	No	Quantity	Rate	Amount
1	Providing, supplying Cabinet with Doors and Formica with all necessary accessories as per design and instruction of the Site Engineer.	Sqft	1	119.53	2500.00	298825
3	Providing, supplying and fixing Mirrors with Wooden Frame with formica, glass and all hardware accessories, complete in all respects as per approved design and instruction of the Site Engineer.	Sq ft	1	150.43	900.00	135387
4	Providing, supplying and fixing Full Length Sheer curtains with curtain rods, hooks, rings, and all necessary accessories, complete in all respects as per approved design and instruction of the Site Engineer.	sq ft	1	465.01	1350.00	627763.5
5	Providing and fixing PVC panel , including all necessary framing, fixing accessories, and finishing works, complete as per approved design and instruction of the Site Engineer.	sq ft	1	236.68	700.00	165676
7	Providing and applying wall putty with paint prepared plastered surface to achieve smooth finish, including necessary surface preparation, sanding, and finishing, complete as per approved design and instruction of the Site Engineer.	sq ft	1	905.21	190.00	171989.9
8	Providing and laying Strip lighting with all necessary electrical works as approved by the design and instruction of site engineer	Rft	1	110.88	1100.00	121968
9	Providing and fixing AC of 1.5 MT capacity with all necessary electrical works,support frame as approved by the design and instruction of site engineer	Nos.	1	3.00	110000.00	330000
10	Fixing and installation of dry wall partition complete with aluminium framing and cement board including all necessary fixtures as per the instruction of site engineer	Sqft	1	195.00	580.00	113100
					Total	1964709

SN	Description	Unit	No	Quantity	Rate	Amount	Remarks
1	Fixing and installation of dry wall partition complete with aluminium framing and cement board including all necessary fixtures as per the instruction of site engineer	Sqft	1	249.16	580.00	144512.8	
2	Providing, supplying and fixing Full Length curtains with curtain rods, hooks, rings, and all necessary accessories, complete in all respects as per approved design and instruction of the Site Engineer.	Sq ft	1	73.30	1550.00	113615	
					Total	258127.8	

WASHROOM-AOC

SN	Description	Unit	No	Quantity	Rate	Amount	Remarks
1	Providing, supplying and fixing Decorative Mirror with necessary supports, fittings, and accessories, complete as per approved design and instruction of the Site Engineer.	No	1	1.00	12500.000	12500	
2	Providing, supplying and installing wall decoration with all necessary paintings fixtures as per the instruction of site engineer	Sqft	1	66.67	450.000	30001.5	
Total:						42501.5	